


BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Project Division
SCHEDULE-B

NAME OF THE WORK : Formation of internal roads Levelling & Lowering of Mallasandra Waste disposal site in Sy No.33 in Ward No.13

Sl No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification	Cum	10194.18	166.42	Rupees One Hundred Sixty Six And Paise Forty Two Only
2	Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density)	Cum	2273.69	320.12	Rupees Three Hundred Twenty And Paise Twelve Only
3	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	Cum	360.83	170.92	Rupees One Hundred Seventy And Paise Ninety Two Only
4	Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications	Sqm	805.67	5.30	Rupees Five And Paise Thirty Only
5	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	120.85	1768.08	Rupees One Thousand Seven Hundred Sixty Eight And Paise Eight Only


EXECUTIVE ENGINEER
KRIBL, BBMP DIVISION
BENGALURU-560 010


Executive Engineer
Dasarahalli Project Division

	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs. with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms [^] thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	120.85	5348.76	Rupees Five Thousand Three Hundred Forty Eight And Paise Seventy Six Only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Ton's	2.14	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three And Paise Forty Two Only
8	Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 25mm and down size graded granite metal coarse aggregate with superplasticizer at 3lts conforming to IS 9103- 1999 reaffirmed 2008, (Coarse and fine aggregate conforming to IS:383) mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications	Cum	120.85	7110.48	Rupees Seven Thousand One Hundred Ten And Paise Forty Eight Only
9	Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	694.00	95.40	Rupees Ninety Five And Paise Forty Only

EXECUTIVE ENGINEER-4
 Signatory of the Contractor
 KRIDE, BBMP DIVISION
 BENGALURU-560 010

Executive Engineer
 Dasarahalli Project Division